



Haul Roads

July 2015



May 2016




Haul roads v9f – to east side of Erato

Haul roads v10 – to west side of Erato

What does this change mean?


- 1 The haul road will be shorter and the gradient of the road has been improved haulage of material from the open pit to the BRSF will take less time and energy (fuel)
- The haul road will be constructed from non acid generating rock from the open pit, while the BRSF platform is constructed
- 3 All Potentilla porphyrantha plants have been translocated along the line of the haul road
- 4 The haul road and crushing building will be more visible to the west side of the mountain





Phase 1 - at year 1

Phase 3 - at year 6 (closure)




Photomontage of BRSF at restoration (after year 6) – from the top of ski lift



The route of the conveyor

July 2015



May 2016



What does this change mean?

- 1 Single line conveyor, fully enclosed constructed at ground level, with passing places for vehicles, herders, animals and wildlife
- 2 Conveyor operates down hill and generates electricity <3MW installed.
- 3 The line of the conveyor and other infrastructure passes through approximately 25 plots of privately owned land



The heap leach facility (HLF)

